

Project : Construction of G+1 Villa
Location : Plot No. 1 @ Beach Palace, Ajman
Client : M/s. H.H.SH. Rashid Bin Humaid Al Nuaimi
Consultant : Eng. Adnan Saffarini

Subject : Quotation for Cooling System & Circulation Pumpset.

Dear Sir,

With reference to the above mentioned project, we would like to give our best prices, delivery terms and conditions for **Supply, Installation & Commissioning of Cooling System, Supply & Commissioning Circulation Pump Set.**

Kindly refer to the attached sheet for details

Terms & Conditions :-

Delivery :
Payment :

Validity :
Warranty :

We hope this will meet with your approval and waiting for your valuable order.

SL	Description of Items	Qty	UNIT PRICE	TOTAL AMOUNT
1	<u>Supply, Installation & Commissioning of Cooling System:</u>	1 No.		
	12.5 Ton Water Chiller 380 V, 3 Ph, 50HZ (SABCON-UAE)			
	Compressor : Copeland-USA			
	Shell body : Stainless Steel			
	Electric Power : 17 kW			
	Tube inside pipe : Copper			
	Refrigerant : R – 407			
	Warranty : 1 year from the date of TOC			
	Delivery :			
	TOTAL AMOUNT			CHILLER IN AED.
			5%VAT IN AED.	
TOTAL AMOUNT INCLUDING 5%VAT IN AED.				
2	CIRCULATION PUMP SET FOR CHILLER :- (1D + 1S + Control Panel + 24 Hrs Timer) (Supply & Commissioning) Pump Brand : XYLEM GOULDS – ITALY Model : 5HM03N04T Horizontal Multi Stage (SS316) Type 1.75 L/s @ 15 mtr 0.40 kW / 0.53 HP, 3 ph – 50 Hz, 2900 Rpm, 2 Pole Inlet & Outlet : 1 ¼ “ x 1 ¼ “ Header : PPR Pipe Works	01 No		
	Warranty : 1 year + 4 years extended (Total 5 years from the date of TOC)			
	Delivery :			
	TOTAL AMOUNT FOR CIRCULATION PUMP SET IN AED.			
	5%VAT IN AED.			
	TOTAL AMOUNT INCLUDING 5%VAT IN AED.			
	TOTAL AMOUNT FOR CHILLER + CIRCULATION PUMP (INCLUDING 5%VAT) IN AED.			

Scope of work:-

1. Supply and Installation with commissioning of Chiller & pumpset
2. Installation & commissioning with standard PVC pipe line work chiller to tank and tank to chiller
3. Electrical wiring from isolator to chiller & Pumpset

Exclusions:

1. Insulation of Water Tank & Water supply piping on Roof
2. Existing tank water clearing
3. Piping works from main supply line to water tank
4. Making foundation and protection cover for the units
5. Permission from authorities.
6. Loading, unloading the equipment & shifting to roof.
7. All types of Civil, Plumbing and Electrical works other than mentioned in our scope of work.

We hope this will meet with your approval and waiting for your valuable order.